



## INSTALLATION ADVISORY

August 2, 2017

To: Versico Authorized Contractors

Attention: Foreman and Project Supervisors

**Re: Updated Polyiso Jobsite Storage Guidelines**

Please share this information with your crews to achieve the best results when working with Versico's Polyiso insulation products. Material should be kept dry at all times. As insulation bundle packaging is intended for transportation only, the following precautions are required when outdoor storage is necessary:

1. Store bundles flat and upright with the bottom of the bundles elevated (2" or more) above a finished surface.
2. Slit the bundle packaging vertically down the center of the two short sides to prevent moisture accumulation within the package.
3. Completely cover the bundle with a waterproof tarp and secure to prevent wind damage and/or displacement.

If you have any questions, or for more information, please contact Chad Buhrman at 717-245-7235 or [chad.buhrman@carlisleccm.com](mailto:chad.buhrman@carlisleccm.com).

Sincerely,

Chad Buhrman  
CCM Insulation Product Manager